

4-060488

1-3-94 15-065-01368-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- 8-19-44

SE SW NE /4 SEC. 14, 09 S, 21 W
2970 feet from S section line
1650 feet from E section line

Operator license# 3300 Lease Balthazor well # 1

Operator: Lloyd Drilling Company County Graham

Address: St. Peter Route Well total depth 3738 feet ^{121.49}
Box 59 Conductor Pipe: 0 inch @ 0 feet
Morland, Kansas 67650 Surface pipe 8 5/8 Inch @ 1649 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pullers, Inc. License# 6050

Address: P.O. Box 347 - Chase, Kansas 67524

Company to plug at: Hour: 12:00P.M. Day: 3 Month: January Year: 94

Plugging proposal received from: Mike Kelso

Company: Kelso Casing Pullers, Inc. Phone: 316-938-2943

Were: Order 215 sxs. 60/40 posmix - 10% gel - 1200# gel and hulls.
Plug while pulling casing.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 4:15P.M., Day: 3, Month: January, Year: 94

Actual plugging report: 8 5/8" to 1649'. 5 1/2" to 3733'. Sand to
3680' & spot 5 sxs. cement with dump bailer. Shot casing at 1946' and
pulled to 1700'. Mix and pump 12 sxs. gel in fresh water followed by
50 sxs. cement with 100# hulls and displaced to 1550'. Pulled casing to
925' and pump 75 sxs. cement. Pull to 450' and circulated cement with
55 sxs. cement. Pulled casing and topped with 15 sxs.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO

Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO

Plugged through TUBING , CASING X. Elevation: 2208 ^{GL}

I did observe the plugging.

INVOICED
DATE 1-28-94
INV. NO. 39821

RECEIVED
STATE CORPORATION COMMISSION
1/10/94
JAN 10 1994
DA (agent)
CONSERVATION DIVISION
Form CP-273
Wichita, Kansas