

15-065-01354-0000

4-041973

4-24

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 09-11-53

SW SE SW /4 SEC. 07 , 09 S, 21 W
330 feet from S section line
1650 feet from W section line

Operator license# 6931

Lease: Cooley Well # 1

Operator: Bowman Oil Company

County: Graham 124.38

Address: 805 Codell Road
Codell, Kansas 67630

Well total depth 3827 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 162 Feet
W/125 sxs cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day: 24 Month: April Year 1998

Plugging proposal received from: Don Bowman

Company: Bowman Oil Company Phone: -

Were: 5 1/2" casing set at 3826' w/125 sxs cement. Perfs at 3699' - 3827'.
Anhy at 1825' - Dakota at 1053'.
Ordered 225 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls - and 14 sxs gel.

Plugging Proposal Received by: Dennis Hamel
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 10:15 A.M., Day: 24, Month: April, Year: 1998

Actual plugging report: Rigged up cementers to 5 1/2" casing. Squeezed 25 sxs cement with 200# hulls, followed with 14 sxs gel, followed with 175 sxs cement with 200# hulls. Max. P.S.I. 300#. S.I.P. 100#. 8 5/8" S.P. Pressured-up to 700#.

Remarks:
Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES X, CALC, NO
Plugged through TUBING CASING X. Elevation: G.L.

I did [X] / did not [] observe the plugging.

Dennis J. Hamel
(agent)

INVOICED
DATE MAY 14 1998
INV. NO. 50554
4-24

Form CP-2/3
5/13/98