

4-041642

12-20 15-065-00944-00-0

E-14,977

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-
C.E2 NW NW
N2 NW /4 SEC. 07 , 09 S, 21 W
660 feet from N section line
990 feet from W section line

Operator license# 3929 Lease Shaw well # 2

Operator: Wildhorse Oil Company County Graham

Address: Box 187 Well total depth 3852 feet ^{125.19}
Bogue, Kansas 67625 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 278 feet
w/175 sxs.

Aband. oil well , Gas well , Input well X, SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 10:00A.M Day: 20 Month: December Year: 94

Plugging proposal received from: Dave VanLaunen

Company: Phone:

Were: 5 1/2" casing set at 3852' w/175 sxs. cement. Perf. at 3641' -
3679'. Anhy. at 1810' - Dakota @ 1000' - W.L.M. 3675'.
Casing squeeze at 1115' w/100 sxs. cement. Records confirm additional
casing repair at various intervals - records indicate shallow squeeze
also.
Ordered 300 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 2:30P.M., Day: 20 , Month: December , Year: 94

Actual plugging report: 8 5/8" S.P. - squeezed 25 sxs. 60/40 pozmix -
10% gel. Max. P.S.I. 500#. S.I.P. 500#. 5 1/2" casing - squeezed
275 sxs. 60/40 pozmix - 10% gel with 500# hulls. Max. P.S.I. 250#.

RECEIVED
STATE CORPORATION COMMISSION
1/5/95
JAN 05 1995

Remarks: Check T.O.F. 20' (12-21-94)
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X , CALC , NO Dakota plug: YES X , NO
Plugged through TUBING , CASING X . Elevation: 2276 GL

I did X did not observe the plugging.

Dennis L. Hamel
(agent)

INVOICED
DATE 1-9-95

INV. NO. 42027
12-20 MAR 16 1996