

4-041749

D-24,575

API Number: 15-163-22856-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

2-8

NW _____ /4 SEC. 22, 09 S, 19 W
3960 feet from N section line
4290 feet from W section line

Operator license# 30742

Lease: Bartos Well # 3

Operator: Palomino Petroleum, Inc.

County: Rooks

Address: 4924 SE 84th Street
Newton, Kansas 67114-0882

Well total depth 3889 ^{126.39} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 935 feet

Aband. oil well____, Gas well____, Input well____, SWD X, D & A____

Plugging contractor: Halliburton Cementing License# _____

Address: Hays, Kansas 67601

Company to plug at: Hour: 9:00 A.M. Day: 8 Month: February Year 1996

Plugging proposal received from: Rick Schreiber

Company: Palomino Petroleum, Inc. Phone: _____

Were: 5 1/2" casing set at 3888' w/150 sxs cement. Perfs at 3802' - 3822'. Perf Anhy. at 1550' - Dakota at 950'. 2 7/8" fiberglass parted at 1250'. Drilled out fiberglass to 1850' - casing parted, drilling on metal. Ordered 250 sxs 60/40 pozmix - 8% gel with 1/4# F.C. plus 500# hulls - also, 100 sxs common with 1/4# F.C. plus 3% c.c.

Plugging Proposal Received by: Herb Deines/Dennis Hamel

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 3:00 P.M., Day: 8, Month: February, Year: 1996

Actual plugging report: Perforated anhy. at 1550' and base S.P. at 950'. R.I.H. with tubing to 1800'. Spotted 100 sxs common with 1/4# F.C. Pulled tubing to 1200' - spotted 200 sxs cement to circulate cement at surface and annulus. Pulled tubing and squeezed casing and annulus with 50 sxs cement to 1100# P.S.I.

Remarks: _____

Condition of casing(in hole): GOOD _____ BAD X Anhy.plug: YES 1528 NO _____

Bottom plug(in place): YES X, CALC _____, NO _____ Dakota plug: YES X, NO _____

Plugged through TUBING X, CASING _____ Elevation: _____ GL

I did[X] / did not[] observe the plugging.

Dennis L. Hamel
(agent)

Form CP-2/3

INVOICED

DATE 2-28-96

INV. NO. 44899

DD

RECEIVED
KANSAS CORP COM
2-14-96
1996 FEB 14 P 12:08