

15-065-19127-00-01

9-16-87

6 040799

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- C 7430

W/2 SW, SEC. 13, T 9 S, R 21 W/E

330 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6234

Lease Name Brault Well # 2 SWD

Operator: The Maurice L. Brown Co.  
Name &

County Graham 136.99

Address 200 Sutton Place

Well Total Depth 4215 feet

Wichita, Kansas 67202

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 92' w/50 sks

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Cement License Number

Address Hays, Kansas

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from Steve Park

(company name) Maurice L. Brown Co. (phone) 316-265-4651

were: 7" casing at 3785' w/500 sks cement 1st stage; 1175 sks cement 2nd stage;

5 1/2" casing on pkr at 3770'; 2 7/8" F. G. Tubing and Baker A D pkr at 3750';

D V tool at Anhy; Top of fish at 1440' (F. G. Tubing);

Perf casing at 1430' (4 holes); at 1100' (3 holes); at 95' (3 holes).

Ordered 250 sks 65/35 Pozmix 10% Gel w/1/4# Flocele and 8 sks Hulls.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 8:00 PM Day: 16 Month: Sept Year: 19 87

ACTUAL PLUGGING REPORT Pumped in 75 sks 65/35 Pozmix 10% Gel w/1/4# Flocele followed w/50 sks cement w/4 sks Hulls. Cement circulated.

Shut-in annulus pumped add. 125 sks cement w/4 sks Hulls.

Max Psi 500#.

Elevation 2197' G. L.

RECEIVED STATE CORPORATION COMMISSION 10-9-87 OCT 9 1987

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED (did not observe this plugging.)

DATE 10-12-87

Signed Dennis L. Hamel (TECHNICIAN)

INV. NO. 18481

Dennis L. Hamel