

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-_____

SW, Sec. 13, T 9 S, R 21 W/E

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5457

Lease Name BALTHAZOR Well # 2

Operator: MONSANTO OIL CO.
Name & Address 3545 N. W. 58TH ST.
OKLAHOMA CITY OKLA. 73112

County GRAHAM

Well Total Depth 3766 feet 12240

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 175'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor ALLIED CEM. License Number _____

Address RUSSELL KANSAS

Company to plug at: Hour: PM Day: 6 Month: 5 Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO RON STRAHAN

(company name) MONSANTO OIL CO. (phone) _____

were: PUMP CEM. MIX DOWN 4 1/2 CASING AND ANNULUS
OF 8 5/8 AND 4 1/2. 325 SX. IN 4 1/2. 75 SX. IN ANNULUS
RAN PACKER AND TUBING TO 585 AND SQUEEZED
BOTTOM PULLED PACKER AND SQUEEZED TOP AND ANNULUS
500# MAX. SHUT IN 500# CASING 150# ON ANNULUS
CEM > 50/50 P02 67 BEL 3% C

Signed Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 4:45 PM Day: 6 Month: 5 Year: 19 83

ACTUAL PLUGGING REPORT AS ABOVE

Remarks: _____

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed Carl Goodrow
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82

INVOICED

RECEIVED
STATE CORPORATION COMMISSION

DATE 5-19-83
INV. NO. 4263-W

MAY 16 1983
5-16-83
CONSERVATION DIVISION
Wichita, Kansas