

4- 060366

12-4

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-22,701-00-00
100'S.&30'W.of
NE NW SW /4 SEC. 13 , 09 S, 21 W
2210 feet from S section line
4340 feet from E section line

Operator license# 6111 Lease Brault well # 1

Operator: N-B Company County Graham

Address: Box 506 Well total depth 3715 feet ^{120.74}
Russell, Kansas 67665 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 218 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Emphasis Oil Operations License# 8241

Address: Russell, Kansas 67665

Company to plug at: Hour: 4:45P.M. Day: 4 Month: December Year: 92

Plugging proposal received from: Jack Fox

Company: Emphasis Oil Operations Phone: 913-483-5345

Were: Order 215 sxs. 60/40 posmix - 6% gel. - 1/4# flocele per. sx.
Space all plugs with heavy drilling mud thru drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 4:45P.M., Day: 4, Month: December, Year: 92

Actual plugging report:

- 1st. plug @ 3695' w/25 sx. - Arbuckle at 3708'.
- 2nd. plug @ 1700' w/25 sx. - Anhydrite 1686' - 1720'.
- 3rd. plug @ 885' w/100 sx. - Dakota 583' - 883'.
- 4th. plug @ 270' w/40 sx. - Surface pipe to 218'.
- 5th. plug @ 40' w/10 sx.
- Rathole with 15 sacks.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD Anhy. plug: YES X NO

Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO

Plugged through TUBING , CASING . Elevation: 2158 GL

I did[] / did not[X] observe the plugging.

DATE 1-8-93

INV. NO. 3715-3

RECEIVED
STATE CORPORATION COMMISSION
12-8-92
DEC 8 1992
CONSERVATION DIVISION
Kansas
E.A.H.

[Signature]

(agent)