

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01367-00-00
Spot: CSESENW Sec/Twnshp/Rge: 13-9S-21W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: EICHMAN Well Number: 3
County: GRAHAM Total Vertical Depth: 3715 feet

Operator License No.: 5285
Op Name: HANSEN, DANE G. - TRUST
Address: PO BOX 187
LOGAN, KS 67646

Production Casing Size: 5.5 feet: 3712 150 SX CMT
Surface Casing Size: 8.625 feet: 245 150 SX CMT

20.74

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/26/2003 9:00 AM

Plug Co. License No.: 5285 Plug Co. Name: HANSEN, DANE G. - TRUST

Proposal Rcvd. from: RICHARD L. WALLGREN, S Company: HANSEN, DANE G. - TRUST Phone: (785) 689-4816

Proposed Plugging Method: Ordered out 200 sxs 60/40 pozmix - 10% gel - 400# hulls - 17 sxs gel.
Well squeezed:
1100'-1129' w/200 sxs cement.
1310'-1339' w/750 sxs cement.
1379'-1437' w/100 sxs cement.
2549'-2607' w/450 sxs cement.
2839'-3017' w/500 sxs cement.

Plugging Proposal Received By: JAY PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 02/26/2003 1:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

TIH with tubing to 3500'.
Mixed and pumped 17 sxs gel followed by 25 sxs cement with 200# hulls.
Pulled up to 1750' and circulated cement with 100 sxs cement and 200# hulls.
POOH and topped with 50 sxs cement. S.I.P. 200#.
Hooked up to 8 5/8" and pumped 50 sxs cement.
S.I.P. 150#.

RECEIVED
MAR 06 2003
3-6-03
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

1002

Signed Jay Pfeifer
(TECHNICIAN)

INVOICED

DATE 3-6-07

INV. NO. 2003061277

MAR 03 2003

D. G. HANSEN #3 EICHMAN 22 13-9-21W SE SE NW

Contr. C-G DRILLING COMPANY GRAHAM County

E. 2179 Comm. 1-18-50 Comp. 3-24-50 IP 3000 BOFD

DRAW DOWN

Tops	Depth	Datum
ANH.	1682	+ 497
HEEB	3376	- 1197
LANS	3416	- 1237
B/KC	3634	- 1455
CONG.	3664	- 1485
SIMP	3691	- 1512
ARB	3711	- 1532
T.D.	3715	- 1536

Casing
 8" 245 DST 3488-99, OP 20
 MIN, REC 180' OIL, 120'
 OIL CUT MUD & 150'
 WTR: CO 3715
 1000' OIH/15 MIN
 SWB 40 BO/1 HR
 ACID 500

MOREL EAST POOL

+	+	+	+
+	+	+	+

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

U