

10-10

4-070069

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-065-02898-00-00

N2 SW SE /4 SEC. 16, 09 S, 21 W
990 feet from S section line
1980 feet from E section line

Operator license# 7076

Lease: Andreson Well # A-4

Operator: Black Diamond Oil, Inc.

County: Graham 120.71

Address: P.O. Box 641
Hays, Kansas 67601

Well total depth 3714 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 10 Inch @ 160 feet
W/125 sxs.

ABAND. oil well X, Gas well _____, Input well _____, SWD. _____, D&A _____

Plugging contractor: Black Diamond Oil, Inc. License# 7076

Address: P.O. Box 641 - Hays, Kansas 67601

Company to plug at: Hour: 1:30 P.M. Day: 10 Month: October Year: 1997

Plugging proposal received from: Ken Vehgie

Company: Black Diamond Oil, Inc. Phone: _____

Were: Ordered 350 sxs 60/40 pozmix - 10% gel with 800# hulls. 5 1/2" at 3713' w/125 sxs.
Perforated at 1700' and 2000'. 2' open hole completion.
1976 squeezed 1309' w/250 sxs. S.I.P. 2000#.
Dakota at 593' - 888'. Anhy. At 1678' - 1718'. Salt at 1918' - 1968'.

10-17-97

Plugging Proposal Received by: Rich Williams

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 4:00 P.M., Day: 10, Month: October, Year: 1997

Actual plugging report: Ran tubing to 3610' PSTD. Spotted 50 sxs at 3578' w/200# hulls.
Pulled to 2100' - pumped 150 sxs with 400# hulls - circulated cement. PTOH. Squeezed with
25 sxs - Max. P.S.I. 1000#. S.I.P. 500#. Pumped 100 sxs with 200# hulls. Max. P.S.I. 200#.
S.I.P. 100#.

Remarks: Backside was flowing when started.

Condition of casing(in hole): GOOD _____ BAD X
Bottom plug(in place): YES X, CALC _____, NO _____
Plugged through TUBING X, CASING _____
Anhy.plug: YES X NO _____
Dakota plug: YES X, NO _____
Elevation: 2206 GL

I did [X] / did not [] observe the plugging.

Richard Williams
(agent)

Form CP-2/3

INVOICED

DATE OCT 23 1997

INV. NO. 49252
10-10