

10-7

4-041932

15-065-01391-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- N/A

NE SW SW /4 SEC. 16, 09 S, 21 W  
990 feet from S section line  
4290 feet from E section line

Operator license# 7076

Lease: Anderson Well # A-5

Operator: Black Diamond Oil

County: Graham 123.44

Address: P.O. Box 641  
Hays, Kansas 67601

Well total depth 3798 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface Pipe: 8 5/8 Inch 165 Feet  
W/150 sxs cmt.

Aband. oil well , Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Allied Cementing License# \_\_\_\_\_

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00 A.M. Day: 7 Month: October Year 1997

Plugging proposal received from: Ken Vehige

Company: Black Diamond Oil Phone: \_\_\_\_\_

Were: 5 1/2" casing set at 3798' w/125 sxs cement.  
Perfs at 3770' - 3774'. Salt at 2125' - Anhy at 1740' - Dakota at 930'.  
Ordered 300 sxs 60/40 pozmix - 10% gel with 1/4# F.C. - 900# hulls - 12 sxs gel.

10-17-97

Plugging Proposal Received by: Dennis Hamel - Herb Deines  
Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 7:30 P.M., Day: 7, Month: October, Year: 1997

Actual plugging report: R.I.H. with tubing to 3700' - spotted 80' of sand (1000#) - wait 30 minutes. Tag T.O.S. at 3640'. Pulled to 3620'. Spotted 10 sxs of gel - pulled to 3400' - spotted 80 sxs cement with 400# hulls. Pulled to 2150' - spotted 50 sxs cement with 200# hulls. Pulled to 1100' - spotted 70 sxs cement with 200# hulls. Circulated cement at surface. P.O.O.H. with tubing. Squeezed casing with 25 sxs cement. Max. P.S.I. 800#. S.I.P. 800#. 8 5/8" S.P. - squeezed 50 sxs cement with 100# hulls. Max. P.S.I. 400#. S.I.P. 200#.

Note: Emergency permission granted to plug whith rig over hole - Dennis Hamel

Remarks: \_\_\_\_\_  
Condition of casing(in hole): GOOD \_\_\_\_\_ BAD  \_\_\_\_\_  
Bottom plug(in place): YES , CALC \_\_\_\_\_, NO \_\_\_\_\_  
Plugged through TUBING , CASING \_\_\_\_\_  
Anhy.plug: YES \_\_\_\_\_ NO  \_\_\_\_\_  
Dakota plug: YES , NO \_\_\_\_\_  
Elevation: \_\_\_\_\_ G.L. \_\_\_\_\_

I did[  ] / did not[  ] observe the plugging.

Dennis L. Hamel  
(agent)

INVOICED

DATE OCT 23 1997

INV. NO. 49250

10-7