

10-8

15-065-01392-00-00

4-070068

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- -

SE NW SW /4 SEC. 16, 09 S, 21 W
1650 feet from S section line
4290 feet from E section line

Operator license# 7076

Lease: Andreson Well # A-6

Operator: Black Diamond Oil, Inc.

County: Graham 121.00

Address: P.O. Box 641
Hays, Kansas 67601

Well total depth 3723 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 10 Inch @ 130 feet
W/125 sxs.

ABAND. oil well X, Gas well _____, Input well _____, SWD. _____, D&A _____

Plugging contractor: Black Diamond Oil, Inc. License# 7076

Address: P.O. Box 641 - Hays, Kansas 67601

Company to plug at: Hour: 10:00 A.M. Day: 08 Month: October Year: 1997

Plugging proposal received from: Ken Vehgie

Company: Black Diamond Oil, Inc. Phone: _____

Were: Ordered 300 sxs 60/40 pozmix - 10% gel with 900# hulls - 10 sxs gel - 10 sxs sand. Perforated at 1700' and 2000'. Dakota at 593' - 888'. Anhy. At 1678' - 1718'. Salt at 1918' - 1968'.

10-17-97

Plugging Proposal Received by: Rich Williams
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 4:00 P.M., Day: 08, Month: October, Year: 1997

Actual plugging report: Ran tubing PBTD 3716'. Spotted 10 sxs sand. Pulled to 3600'. Allied pumped 10 sxs gel with 300# hulls. Pulled to 3420'. Mixed 80 sxs 60/40 pozmix - 10% gel with 200# hulls. Pulled to 2100' - pumped 50 sxs with 200# hulls. Pulled to 1100' - pumped 60 sxs with 200# hulls - circulated cement. PTOH. Squeezed with 25 sxs. Max. P.S.I. 400#. S.I.P. 250#. Hooked-up to 8 5/8" - pumped 50 sxs with 100# hulls. Max. P.S.I. 400#. S.I.P. 200#.

Remarks:
Condition of casing(in hole): GOOD _____ BAD X
Bottom plug(in place): YES X, CALC _____, NO _____
Plugged through TUBING X, CASING _____
Anhy.plug: YES X NO _____
Dakota plug: YES X, NO _____
Elevation: 2220 GL

I did [X] / did not [] observe the plugging.

Richard Williams
(agent)
Form CP-2/3

INVOICED

DATE OCT 23 1997

INV. NO. 49251

10-8