

10-10

15-065-01397-00-00

4-070067

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- -

NE NW SW /4 SEC. 16, 09 S, 21 W
2310 feet from S section line
4290 feet from E section line

Operator license# 7076

Lease: Andreson Well # A-11

Operator: Black Diamond Oil, Inc.

County: Graham 122.95

Address: P.O. Box 641
Hays, Kansas 67601

Well total depth 3783 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 10 Inch @ 170 feet
W/125 sxs.

ABAND. oil well X, Gas well _____, Input well _____, SWD. _____, D&A _____

Plugging contractor: Black Diamond Oil, Inc. License# 7076

Address: P.O. Box 641 - Hays, Kansas 67601

Company to plug at: Hour: 8:30 A.M. Day: 10 Month: October Year: 1997

Plugging proposal received from: Ken Vehgie

Company: Black Diamond Oil, Inc. Phone: _____

Were: Ordered 300 sxs 60/40 pozmix - 10% gel with 600# hulls.
5 1/2" at 3782' w/125 sxs. D.V. 1765' w/500 sxs. Did not circulate cement.
Dakota at 600' - 895'. Anhy. At 1685' - 1725'. Salt at 1918' - 1968'.
Perfs at 3723' - 3745'.

10-17-97

Plugging Proposal Received by: Rich Williams
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 11:00 A.M., Day: 10, Month: October, Year: 1997

Actual plugging report: Ran tubing to 3710'. Spotted 50 sxs 60/40 pozmix - 10% gel with 200# hulls. Pulled to 2100' - pumped 145 sxs with 400# - cement circulated. PTOH. Squeezed 50 sxs Max P.S.I. 600#. S.I.P. 300#. Pumped 5 sxs down 8 5/8". Max. P.S.I. 500#. S.I.P. 500#.

Remarks:
Condition of casing(in hole): GOOD _____ BAD X
Bottom plug(in place): YES X, CALC _____, NO _____
Plugged through TUBING X, CASING _____
Anhy.plug: YES X NO _____
Dakota plug: YES X, NO _____
Elevation: 2227 GL

I did [X] / did not [] observe the plugging.

INVOICED

Richard Williams
(agent)

Form CP-2/3

DATE OCT 23 1997
INV. NO. 49255
10-10