

4-032035

12-9 15-065-02901-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 1944

SE NW NE /4 SEC. 16 , 09 S, 21 W  
4290 feet from S section line  
1650 feet from E section line

Operator license# 5135

Lease Boland well # 1

Operator: John O. Farmer, Inc.

County Graham

Address: P.O. Box 352  
Russell, Kansas 67665

Well total depth 3692 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 10 3/4 Inch @ 180 feet

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: Allied Cement Company License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 9 Month: December Year: 94

Plugging proposal received from: Duane Eichman

Company: John O. Farmer, Inc. Phone:                     

Were: Order 350 sxs. 60/40 pozmix - 10% gel - 500# hulls.  
Order work string.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[ X ], Part[      ], None[      ]

Completed: Hour: 12:30P.M., Day: 9, Month: December, Year: 94

Actual plugging report: 10 3/4" set at 180' w/125 sxs. cwc. 5 1/2" set  
at 3674' w/150 sxs. Prod. perfs. 3503' - 3692'. Critical area control  
shots at 1675' and 900' - ran tubing to 2320'. Mixed and pumped down  
2 7/8" with 120 sxs. Lay down tubing to 1160' - mixed and pumped  
130 sxs. to circulate. Pulled tubing - squeezed 5 1/2" with total 300  
sxs. cement blend with 500# hulls mixed in to Max. P.S.I. 300#. Close  
in P.S.I. 100#. Squeezed 10 3/4" with 50 sxs. cement blend with 100#  
hulls to Max. P.S.I. 300#. Close in P.S.I. 100#. Plug complete.

Remarks:  
Condition of casing(in hole): GOOD X BAD      Any plug: YES X NO       
Bottom plug(in place): YES     , CALC X, NO      Dakota plug: YES X, NO       
Plugged through TUBING     , CASING X. Elevation:      GL

I did X observe the plugging. Carl Goodrow

**INVOICED**  
DATE 1-31-95  
INV. NO. 43115

(agent)  
Form CP-2/3

STATE CORPORATION COMMISSION  
JAN 30 1995  
CONSERVATION DIVISION