

4-070152

8-18

15-065-019270000 <sup>01</sup>

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 05-1949

S2 SW NW /4 SEC. 16, 09 S, 21 W  
2970 feet from S section line  
4620 feet from E section line

Operator license# 5030

Lease: Clack Well # B-1

Operator: Vess Oil Corporation

County: Graham

Address: 8100 E. 22<sup>nd</sup> Building #300  
Wichita, Kansas 67226

Well total depth 3704 <sup>120.38</sup> feet  
Conductor Pipe: 0 inch @ 0 sxs.  
Surface pipe 8 5/8 Inch @ 252 feet  
W/150 sxs.

ABAND. oil well , Gas well , Input well , SWD. , D&A

Plugging contractor: Smoky Hills Well Service License# 5030

Address: P.O. Box 307 - Natoma, Kansas 67651

Company to plug at: Hour: 9:00 A.M. Day: 18 Month: August Year: 1999

Plugging proposal received from: Joel Stull

Company: Smoky Hills Wells Service Phone: 785-885-4352

Were: 5 1/2" casing set at 3684' w/150 sxs. Top of cement 2904'.  
Squeeze 1961 at 1093' - 1107' w/175 sxs.  
Squeeze 1994 at 3302' - 3342' w/150 sxs.  
Arb. O.H. 3684' - 3688'. CIBP 3648'. KC Perfs at 3392' - 3600'.  
Casing leaks at 2950' - 2970'. Fluid level 300'.  
Ordered out 365 sxs 60/40 pozmix - 10% gel with 500# hulls.

Plugging Proposal Received by: Rich Williams

Plugging operations attended by agent? All , Part , None

Completed: Hour: 2:15 P.M. Day: 18, Month: August, Year: 1999

Actual plugging report: Perforated 900' - 1700' - 2000'. Ran tubing to 3648'. Tagged and pulled to 3630'. Copeland cement pumped 100 sxs 60/40 pozmix - 10% gel with 150# hulls. Lost circulation. Pulled to 2097' and pumped 100 sxs cement. Again lost circulation. Pulled to 1720' and pumped 125 sxs cement. Cement circulated. PTOH. Squeezed 40 sxs cement with 100# Max. Shut in.

08-24-99 - Checked casing cement - fell back to 350' from surface.

08-25-99 - Redimix with 2 yards of cement at 2:35 P.M.

Remarks: Check backside and confirmed cement on backside.

Condition of casing(in hole): GOOD  BAD  Anhy.plug: YES  NO

Bottom plug(in place): YES , CALC , NO  Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: 2204 GL

I did  / did not  observe the plugging.

*Richard Williams*  
(agent)

**INVOICED**

DATE 8-31-99

INV. NO. 60457

Form CP-273  
8-31-99