

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22559-00-00
Spot: SWNENW Sec/Twnshp/Rge: 22-9S-21W
990 feet from N Section Line, 1650 feet from W Section Line
Lease/Unit Name: DARNELL A Well Number: 7
County: GRAHAM Total Vertical Depth: 3980 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

Production Casing Size: 5.5 feet: 3972 150 SX CMT
Surface Casing Size: 8.625 feet: 272 150 SX CMT
#129 35

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/16/2003 8:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 483-9168

Proposed Plugging Method: Ordered 175 sxs 60/40 pozmix - 10% gel - 300# hulls - 25 sxs gel.
DV at 1725' cwc. WLM at 3880'. TOF at 1800'.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 07/16/2003 10:00 AM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Rigged up cementers.
Squeezed 5 1/2" casing with 25 sxs cement with 200# hulls, followed with 25 sxs gel, followed with 60 sxs cement.
Max. P.S.I. 2000#. S.I.P. 1200#.
Rigged up to 8 5/8" - pressured up to 800# - no cement.

RECEIVED
AUG 13 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Dennis L. Hamel
(TECHNICIAN)

INVOICED

102
DATE 8-13-03
INV. NO. 2004060399


Form CP-2/3

AUG 08 2003

STATE KANS COUNTY GRAHAM
FIELD MOREL (MULTIPAY)
OPER OXY USA
WELL 7 DARNELL "A"
API 15-065-22559-0000
SPUD 03/21/1990
DTD 3980 LTD FTD ARBUCKLE

22-9S-21W
SW NE NW
4290FSL 3630FEL SEC

WELL CLASS DO
STATUS OIL
COMP 10/01/1990
FBTD



LOC 7 MI SE BOGUE, KS

Petroleum Information Corporation
A Division of Schlumberger

IP IPP 22 BOPD 97 BW
PROD ZONE: ARBUCKLE 3790-3792

EL: 2280 KB 2275 GR

CSGS: 8 5/8 @ 272 W/ 150 SACKS
5 1/2 @ 3972 W/ 150 SACKS
DRLG COMP 3/27/90 RIG REL 3/27/90

LOG TOPS:
TOPEKA 3225 -945
OREAD 3381 -1101
HEEBNER 3434 -1154
TORONTO 3457 -1177
LANSING 3472 -1192
ARBUCKLE 3771 -1491
TD 3980 -1700

PERFS: ARBUCKLE PERF W/ 4/FT 3790-3792
ACID 200 GALS 15% NE

NO CORES OR DSTS

LOG TYPES: DI GR CDL MICL

OPER ADDRESS: 110 S MAIN, STE 800, WICHITA, KS 67202

CONTR: ALLEN DRLG GEOL: BILL KELLER

KS 4-102390

Copyright 1990 Petroleum Information Corporation