

12-27 15-065-01478-00-00

6 041119

6-28-57

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
SE NE SE, SEC. 22, T 9 S, R 21 W 21

TECHNICIAN'S PLUGGING REPORT

1650 feet from S section line
330 feet from E section line

Operator License # 5465

Lease Name Sutor A Well # 2-3 KCC ZAP

Operator: John B. Collins
Name & Address: 1503 Vine St.
Suite B
Hays, Ks. 67601

County Graham 123.53

Well Total Depth 3801 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 169' w/ cement

Abandoned Oil Well Gas Well Input Well SWD Well D&A M.A.

Other well as hereinafter indicated

Plugging Contractor Allied Cement License Number

Address Russell Ks.

Company to plug at: Hour: 10:00AM Day: 26 Month: Dec Year: 19 89

Plugging proposal received from I. B. Collins

(company name) Same (phone)

were: 5 1/2" casing set at 3800' w/MA sks. Top perf at 3664' - 82';

4 1/2" casing liner from surface to 3490' w/150 sks cement circ: Holes in casing at 850' - 1250' and 2747' sq w/250 sks. plus 50 sks from surface. Ordered 250 sks 65/35 poz 10% gel w/1/4# f.c. plus 5 sks hulls.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:15PM Day: 27 Month: Dec Year: 19 89

ACTUAL PLUGGING REPORT Ran tubing to 1700' and perf at 1720' - 1400' and 1050'. Pumped in 4 1/2" casing 75 sks cement w/1/4# f.c. plus 1 sk hulls mixed in cement. Max 1700#

S.I. 1500# psi.

RECEIVED STATE CORPORATION COMMISSION 1/17/90 JAN 17 1990

Remarks: (If additional description is necessary, use BACK of this form) CONSERVATION DIVISION Wichita, Kansas

INVOICED

DATE JAN 24 1990

INV. NO. 27110

J.B.S.

Signed Dennis L. Hamel (TECHNICIAN)

Dennis L. Hamel