

4-042006

2-17

02920-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-065-~~97754~~

NE NW NW /4 SEC. 22, 09 S, 21 W
4950 feet from S section line
4290 feet from E section line

Operator license# 5030
Operator: Vess Oil Corporation
Address: 8100 E. 22nd St. North
Building #300
Wichita, Kansas 67226

Lease: Darnell Well # A-3
County: Graham 122.85

Well total depth 3780 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 203 Feet
W/150 sxs.cmt.

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00 A.M. Day: 17 Month: February Year 1999

Plugging proposal received from: Pat Canaday

Company: Vess Oil Corporation Phone: -

Were: Ordered 200 sxs 60/40 pozmix - 10% gel plus 20 sxs gel and 300# hulls.
5 1/2" casing set at 3776' w/100 sxs cement.
O.H. 3776' - 3780'.
Dakota 1000'.

2/23/99

Plugging Proposal Received by: Dennis Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 2:15 P.M. , Day 17, Month: February , Year: 1999

Actual plugging report: R.I.H. with tubing 3700'. Spotted 25 sxs cement with 300# hulls, followed with 20 sxs gel. Pulled to 1800'. Spotted 40 sxs . Pulled to 1000' and circulated with 70 sxs cement. P.O.O.H. with tubing. Squeezed casing with 25 sxs cement. Max. P.S.I. 500#. S.I.P. 300#. 8 5/8" - squeezed 25 sxs with 100# hulls. S.I.P. 250#.

Remarks:
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING CASING . Elevation: G.L.

I did[X] / did not[] observe the plugging.

Dennis J. Hamel
(agent)

Form CP-2/3

INVOICED

DATE 3-1-99

INV. NO. 60671