

9-1 15-065-01446-00-00

6 031155

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1958
SW SW NW, SEC. 19, T 9 S, R 21 W/EX

2970 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Pricer Well # A - 3

Operator: Oxy USA Inc.

County Graham 125.48

Name & Address 3545 NW 58th St.

Well Total Depth 3861 feet

Oklahoma City, Ok 73112

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 set 240

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement Co. License Number

Address Ressel, Ks.

Company to plug at: Hour: AM Day: 1 Month: Sept Year: 19 88

Plugging proposal received from Pringle

(company name) Oxy USA (phone)

were: Order 700 sks 60/40 Poz 8% Gel 500# Hulls. Allied Cement Co.
OWS Water Trucks, Murfin Rig. 8 5/8" set at 240' w/175 sks. 5 1/2" set at 3854' w/200 sks.

D.V. tool 1825' w/400 sks cement and 200 cu.ft. Stratacrete cwc.

RECEIVED
STATE CORPORATION COMMISSION
9/16/88
SEP 16 1988

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:00PM Day: 1 Month: Sept Year: 19 88

ACTUAL PLUGGING REPORT

Ran tubing to 2170'. Circulated cement to surface. Laid down tubing. Tie onto 5 1/2" squeeze with total of 450 sks cement and 600# Hulls to max psi 1000#. Close in psi 600#. Test annulus w/1 Bbl slurry to max psi 1000#. Close in psi 1000#. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED
(If desired) observe this plugging.

DATE 9-22-88
INV. NO. 22378

Signed Carl Goodrow (TECHNICIAN)
Carl Goodrow