

4-032390

D-06,128

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-065-03473-00-01

NE NW NE _____ /4 SEC. 17, 09, 21 W
4950 _____ feet from S section line
1650 _____ feet from E section line

Operator license# 5363

Lease: Cooley "B" Well # 12

Operator: Berexco, Inc. 10-20

County: Graham 123.14

Address: P.O. Box 723
Hays, Kansas 67601

Well total depth 3789 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 165 feet

Aband. oil well _____, Gas well _____, Input well _____, SWD_X _____, D & A _____

Plugging contractor: Berexco, Inc. License# 5363

Address: P.O. Box 723 - Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 20 Month: October Year: 1999

Plugging proposal received from: _____

Company: _____ Phone: _____

Were: Order 350 sxs 60/40 pozmix - 10% gel - 500# hulls.

Order work string.

Allied Cement Company.

D-06,128 canceled by Commission Order Date 07-22-99.

RECEIVED
KANSAS CORPORATION COMMISSION
11/4/99
NOV 04 1999

CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 1:45 P.M., Day: 20 Month: October Year: 1999

Actual plugging report: 8 5/8" set at 165' w/100 sxs cwc. 5 1/2" set at 3738' w/70 sxs.
D.V. Tool at 1750' w/350 sxs. Ran tubing to 3555'. Tag packer stuck in hole. Circulated
to surface. Tied onto 5 1/2". Squeezed with 350 sxs cement blend with 500# hulls mixed in to
Max. P.S.I. 500#. Held. Pressured up on 8 5/8" to 300#. Cement at surface. Plug complete.

Remarks:

Condition of casing(in hole): GOOD _____ BAD _____ Anhy.plug: YES X NO _____

Bottom plug(in place): YES _____, CALC _____, NO _____ Dakota plug: YES X, NO _____

Plugged through TUBING _____, CASING _____ Elevation: _____ GL

I did [X] / did not [] observe the plugging.

Carl Goodrow
(agent)

INVOICED

DATE 12/3

INCL. NO. 60896

Form CP-2/3