

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01955-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 17-9S-21W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: COOLEY Well Number: 2
County: GRAHAM Total Vertical Depth: 3811 feet

Operator License No.: 5058
Op Name: CORSAIR ENERGY, LC
Address: 914 E. DOUGLAS
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 3810 125 SX CMT
Surface Casing Size: 8.625 feet: 149 125 SX CMT

9/23.86

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/05/2003 11:00 AM

Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: JIM COLLINS Company: CORSAIR ENERGY, LC Phone: (316) 267-7779

Proposed: Ordered out 275 sxs 60/40 pozmix - 10% gel - 500# hulls - 16 sxs gel spacer.
Plugging: Fluid level 400' from surface - no squeeze records.
Method: Perforate: Salt at 2000' - Anhy 1560' - Dakota at 1025'.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/05/2003 4:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Log Tech perforated two shots at 2000' - 1560' - 1025'. Ran tubing to 3465'.
Allied pumped 16 sxs gel spacer with 200# hulls, followed with 40 sxs 60/40 pozmix - 10% gel with 200# hulls.
Pulled tubing to 1660'.
Allied pumped 120 sxs cement with 100# hulls - cement circulated.
PTOH. Squeezed with 50 sxs cement.
Max P.S.I. 700#. S.I.P. 400#.
Hooked up to backside - instant pressure - cement in head.

RECEIVED
MAY 21 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

FD

Signed Richard Williams
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 5-22-03
VV. NO. 2003061565

MAY 12 2003

BARNETT OIL CO.

#2 COOLEY

17-9-21W 22
NW NW SE

Contr. BARNETT DRILLING INC.

GRAHAM County

E. 2295 Comm. 3-17-50

Comp. 4-28-50

IP


346 BOPD

PHY POT

Tops	Depth	Datum
ANH	1521	+1774
HEEB	3161	-1169
LANS	3501	-1206
SIMP	3806	-1511
ARB	3809	-1514
TD	3818	-1523

Casing

8" 150 DP 3818, 1800' OIL:
5" 3809 SWB 52 BO/3 HRS.



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

17-9-21W
NW NW SE