

9-24

220  
R

6-031586

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-065-02903-00-00

SW NW SW /4 SEC. 17 S, 21 W  
1650 feet from S section line  
4950 feet from E section line

Operator license# 5565

Lease Cooley well # A-3

Operator: N.C.R.A.

County Graham

Address: 2000 S. Main Street  
P.O. Box 1404  
McPherson, Kansas 67460

Well total depth 3841 feet 124.83  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 173 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 2:00P.M. Day: 24 Month: September Year: 91

Plugging proposal received from: Tom Larson

Company: N.C.R.A. Phone: \_\_\_\_\_

Were: 8 5/8" set @ 173' cwc. 5 1/2" set @ 3833' w/NA top of cement  
at 3400'. Perf's @ 3524' - 3718'. Opened A thru K zones, swab,  
no oil, P & A. Order 600 sx. 65/35 poz. - 10% gel. - 500# hulls.  
Halliburton Cement Company.

Holes in casing through Dakota Cheyenne C.H. to anhy. Received 10/11/91

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All , Part  X ], None

Completed: Hour: 2:00P.M., Day: 24, Month: September, Year: 91

Actual plugging report: Ran tubing, mixed and pumped 100 sx. cement  
blend. Laid down tubing to 1260'. Pumped 300 sx. with hulls to  
circulate. Laid down tubing squeezed 5 1/2" with total of 500 sx.  
cement blend with 300# hulls mixed into Max. P.S.I. 300#. Close in  
P.S.I. 300#. Squeezed 8 5/8" with 100 sx. cement blend to Max. P.S.I.  
300#. Close in P.S.I. 150#. Plug complete.

Remarks: \_\_\_\_\_

I **INVOICED** [ ] observe the plugging. Carl Goodrow

DATE 11-8-91

INV. NO. 33653

*Sub. S*

(agent)  
Form CP-2/3