

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-163-02295-00-00

API NUMBER N/A

LEASE NAME Dan Barry 'C'

WELL NUMBER 3

4290 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 10 TWP. 9S RGE. 19W (E) or (W)

COUNTY Rooks

Date Well Completed 11-12-51

Plugging Commenced 06-26-90

Plugging Completed 07-13-90

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Conoco Inc.

ADDRESS 3817 NW Expressway, Oklahoma City, OK 73112

PHONE#(405) 948-3100 OPERATORS LICENSE NO. 5916

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 06-26-90 (date)

by Dennis Hammel (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Plattsmouth Depth to Top 3132 Bottom 3176 T.D. 3484

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Plattsmouth	Oil	3132	3176	10-3/4"	196'	
				5-1/2"	3467'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. RU. POOH rods & tbg laying down. RD. RU & RIH w/perf gun. Shot 3 holes 50' below the base of the Dakota @831'. Perf'd Anhydrite w/3 holes @1471'. RD. SIW. RU & pumped 50sx 65/35 Poz. w/8% gel, w/1/4# cello flakes & 50# hulls down surface pipe. Hooked up to 5-1/2" & pumped 105sx 65/35 Poz. w/8% gel, & 1/4" cello flakes followed w/300 sx 65/35 Poz. w/10% gel, 1/4# cello flakes & 350# hulls. RD & shutin. Checked cement level in 5-1/2", had dropped 104'. Dump 1-yd. common cement down csg. (If additional description is necessary, use BACK of this form.)

Cut & capped csg 5-1/2' BGL. Buried cement & leveled location, tore out electric powerlines and abandoned lease.

Name of Plugging Contractor B.J.-Titan Services License No. \_\_\_\_\_

Address 1910 18th St., PO Box 169, Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Conoco Inc.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Christopher J. Dodson

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Chris J. Dodson

(Address) 3817 NW Expressway  
Oklahoma City, OK 73112

SUBSCRIBED AND SWORN TO before me this 6th day of August, 19 90

Lucille M. Smith  
Notary Public

My Commission Expires: 12-1-92