

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER N/A

LEASE NAME Dan Barry 'C'

WELL NUMBER 4

3630 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 10 TWP. 9S RGE. 19W (E) or (W)

COUNTY Rooks

Date Well Completed 01-10-52

Plugging Commenced 07-06-90

Plugging Completed 07-13-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Conoco Inc.

ADDRESS 3817 NW Expressway, Oklahoma City, OK 73112

PHONE#(405) 948-3100 OPERATORS LICENSE NO. 5916

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 06-26-90 (date)

by Dennis Hammel (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached?

Producing Formation Lansing, K.C. Depth to Top 3236 Bottom 3477 T.D. 3516

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing-K.C.	Oil	3236	3304	10-3/4"	193	
				7"	3479	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. RU wireline & RIH w/gun, perf'd 50' below base of Dakota @822' w/3 holes & perf'd the Anhydrite @1464' w/3 holes. RD & shutin. RU & pumped 50sx 65/35 Poz. w/8% gel & 1/4# cello flakes & 50# hulls down surface pipe. Hooked on to 7" csg & pumped 50sx common w/1/4# cello flakes, followed w/50sx common w/1/4# cello flakes & 100# hulls. Pumped 470sx 65/35 Poz. w/8% gel & 1/4# cello flakes + 500# hulls down csg. Cut & capped csg 5' BGL, buried cement & leveled location, removed power lines.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor BJ-Titan Services License No.

Address 1910 18th St., P. O. Box 169, Great Bend, KS 67530 STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Conoco Inc.

STATE OF Oklahoma COUNTY OF Oklahoma

Christopher J. Dodson (Employee of Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Chris J. Dodson

(Address) 3817 NW Expressway
Oklahoma City, OK 73112

SUBSCRIBED AND SWORN TO before me this 6th day of August, 19 90

My Commission Expires: 12-1-92

Notary Public