

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER N/A

LEASE NAME Dan Barry 'C'

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 5

4950 Ft. from S Section Line

2310 Ft. from E Section Line

LEASE OPERATOR Conoco Inc.

SEC. 10 TWP. 9S RGE. 19W (E) or (W)

ADDRESS 3817 NW Expressway, Oklahoma City, OK 73112 COUNTY Rooks

PHONE#(405) 948-3100 OPERATORS LICENSE NO. 5916

Date Well Completed 09-13-62

Character of Well Oil

Plugging Commenced 06-26-90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 07-13-90

The plugging proposal was approved on 06-26-90 (date)

by Dennis Hammel (KCC District Agent's Name).

Is ACO-1 filled? Yes If not, is well log attached? -K.C.

Producing Formation Shawnee & Lansing Depth to Top 2989 Bottom 3479 T.D. 3525

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Shawnee	Oil	3143	3170	10-3/4"	207'	
Lansing-K.C.	Oil	3255	3374	7"	3524'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. RU & POOH rods & Tbg laying dn. RD & shutwell in. RU & RIH w/perf gun. Perf'd 50' below the base of the Dakota @840', 3holes 3 holes @1485'. RD. RU & pumped 600sx 65/35 w/8% gel 1/4# cello flakes & 600# hulls. Pumped 75sx 65/35 Poz., 8% gel + 1/4# cello flakes down surface pipe. RD. Checked cement level in 7", dropped 75'. Dumped 5 yds cement down csg. Cut & capped csg 5' BGL, buried cement & leveled location, removed power poles & line, abandon lease.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B.J.-Titan Services License No. 8-7-90

Address 1910 18th St., P O Box 169, Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Conoco Inc.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Christopher J. Dodson (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Chris J. Dodson

(Address) 3817 NW Expressway
Oklahoma City, OK 73112

SUBSCRIBED AND SWORN TO before me this 6th day of August, 19 90

Lucille M. Smith
Notary Public

My Commission Expires: 12-1-92