

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER D-02,739

LEASE NAME Rostocil "C"

WELL NUMBER #6-SWD

#4

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

3630 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 10 TWP. 9s RGE. 19 (E) or (W)

LEASE OPERATOR Gore Oil Company

ADDRESS 202 S. St. Francis, Box 2757, Wichita, KS 67201-2757 COUNTY Rooks

PHONE# (316) 263-3535 OPERATORS LICENSE NO. 5552 Date Well Completed April, 1951

Character of Well SWD Plugging Commenced July 17, 1990

(Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging Completed July 17, 1990

The plugging proposal was approved on July 16, 1990 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? Unknown If not, is well log attached? No

Disposal Formation Arbuckle Depth to Top 3452' Bottom 3801' T.D. 3801'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0'	319'	8 5/8"	319'	0'
		0'	3456'	5 1/2"	3456'	0'
		3335'	3512'	4"	177'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Junk in hole. Top of 3" fibercast tubing @ 1650'. Spot 50 sx "A" plugs at 1640', 1090', 540'. Pump down 5 1/2" casing 50 sx "A", 150 sx 65/35 Pozmix, 8% gel. Shut in with 500 psi. Cement circulated in cellar. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. 7718

Address P.O. Box 428, Hays, KS 67601


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gore Oil Company

STATE OF Kansas COUNTY OF Sedgwick, ss.

Scott W Scheuerman (Employee of Operator) ~~or Operator~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Scott W Scheuerman

(Address) Scott W Scheuerman, Petroleum Engr.
202 S. St. Francis, Wichita, KS 67201



TESTIFIED AND SWORN TO before me this 31st day of July, 19 90

Rebecca K. Crawford
Notary Public

My Commission Expires: 1-7-91