

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec. 10 Twp. 9 Rge. (E) 19 (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines SE SE SE
Lease Owner Harry Gore
Lease Name Hashenbarger Well No. 1
Office Address 400 Brown Bldg., Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 8-23 19 48
Application for plugging filed 8-8 19 49
Application for plugging approved 8-8 19 49
Plugging commenced 8-8 19 49
Plugging completed 8-16 19 49
Reason for abandonment of well or producing formation Oil depleted

If a producing well is abandoned, date of last production July 19 49
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Arbuckle Depth to top 3496 Bottom 3499 Total Depth of Well 3499 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				5 1/2"	3495	1,533'7"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

crushed rock 3513 to 3490
cement, 6 sx 3490 to 3470
mudded 3470 to 185
rock bridge 185 to 175
cement, 15 sx 175 to 140
mud 140 to 30
cement, 10 sx 30 to cellar

RECEIVED
Conservation Div.
8-27-49
AUG 27 1949
STATE CORPORATION
COMMISSION
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Harry Gore
Address 400 Brown Bldg., Wichita, Ks.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Theodore Gore (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Theodore Gore Partner
400 Brown Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of August, 19 49

My commission expires June 7, 1952
Charlotte Ketchka Notary Public.

PLUGGING
FILE SEC 10 T 9 R 194
BOOK PAGE 108 LINE 28

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - HARRY GORE
Farm - Hashenbarger No. 1

SEC. 10 T. 9 R. 19W
SE SE SE

Total Depth. 3499'
Comm. 8-9-48 Comp. 8-23-48
Shot or Treated.
Contractor.
Issued. 10-23-48

County. Rocks
KANSAS



CASING:
8-5/8" 165' Cem. W/125 Sx. Circ.
5-1/2" 3495' Cemented W/100 Sacks

Elevation. _____

Production. Pot. 35 Bbls.

Figures indicate Bottom of Formations.

surface clay	40
sand	60
shale	100
sand & shale	140
shale & shells	165
shale	400
shale & shells	470
shale, shells of pyrite	570
sand	605
shale & sand	750
sand	820
shale & shells	945
sand	1210
shale & shells	1300
sand & shale	1350
shale & red bed	1468
anhydrite	1512
shale & red bed	1550
shale & shells	1810
shale & lime shells	2040
salt & shale	2075
lime & shale	2705
shale & lime shells	2795
lime & shale	3237
lime	3390
lime & shale	3496
arbuckle	3499
Total Depth	

Tops:
Hebner shale 3214
Lansing K. C. 3234
Lansing K. C. #2 3255
Arbuckle 3493

RECEIVED

Conservation Div.

AUG 9 - 1949

STATE CORPORATION
COMMISSION
KANSAS

PLUGGING
FILE SEC 10 T 9 R 19W
BOOK PAGE 108 LINE 28