

15-163-03483-00-00


# WELL PLUGGING RECORD

## FORMATION PLUGGING RECORD

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 Give All Information Completely  
 Make Required Affidavit  
 Mail or Deliver Report to:  
 Conservation Division  
 State Corporation Commission  
 800 Bitting Building  
 Wichita, Kansas

Strike out upper line  
 when reporting plugging  
 of formations.

Rooks County, Sec. 12 Twp. 9 Rge. (E) 19 (W)  
 Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SWc NE $\frac{1}{2}$   
 Lease Owner D.R. Lauck Oil Company Inc. et.al  
 Lease Name Jelinek "A" Well No. 2  
 Office Address Wichita, Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
 Date well completed May 15 19 48  
 Application for plugging filed May 15 19 48  
 Application for plugging approved May 15 19 48  
 Plugging commenced May 15 19 48  
 Plugging completed May 15 19 48  
 Reason for abandonment of well or producing formation dry hole  
 If a producing well is abandoned, date of last production 19  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above  
 Section Plat

Name of Conservation Agent who supervised plugging of this well Rives  
 Producing formation Depth to top Bottom Total Depth of Well 3513 Feet  
 Show depth and thickness of all water, oil and gas formations.

### OIL, GAS OR WATER RECORDS

### CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	water	3481	3513	10"	200	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mud 3513 - 200  
 Bridge 200 - 195  
 Cement 195 - 155  
 Mud 155 - 41  
 Bridge 41 - 36  
 Cement 36 - 6 to bottom of cellar  
 cap welded on top of surface casing

5/19/48

(If additional description is necessary, use BACK of this sheet)


Correspondence regarding this well should be addressed to D.R. Lauck Oil Company Inc.  
 Address 520 Fourth National Bank Building, Wichita 2 Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.  
 E. C. Moncrief (employee of owner) or (owner or operator) of the above-described well,  
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. C. Moncrief  
 Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 18 day of May 19 48  
 Elizabeth Gay Notary Public.

My commission expires Sept. 14, 1951



D. R. LAUCK OIL COMPANY INC.

Jelinek "A" No.2

Sec. 12 T 9S. R 19W  
SW $\frac{1}{4}$  NE $\frac{1}{4}$

Rooks County Kansas

Commenced May 4, 1948

Completed May 15, 1948

Casing 10" 200' cemented 135 sacks

Soil	15
Lime	50
sand	95
Shale & shells	190
lime	223
shale & shells	676
sand	835
shale	885
sand	1135
shale & shells	1250
shale	1265
red rock	1 420
Anhydrite	1453
red rock	1475
shale & shells	1930
shale & salt	2190
shale & shells	2330
shale & lime	2430
lime	2490
shale & shells	2555
lime	2600
shale & lime	3060
shale & shells	3134
lime	3145
shale & lime	3240
lime	3515

Tops- Derrick floor

Heebner	3199
Dodge	3216
Lansing	3238
Arbuckle	3481
Total Depth	3515

Drill stem test

3483-3490

5' mud in 10 minutes

Dry and abandoned

6/22/48  
JUN 22 1948

**PLUGGING**  
FILE SEC 12 T 9 S R 19W  
BLOCK PAGE 29 LINE 38