

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rooks

County. Sec. 26 Twp. 9S Rge. 19W (XXXX) (W)

Location as "NE/CNW/SW" or footage from lines NE NW SE

Lease Owner Herman George Kaiser

Lease Name Thomas Well No. #1

Office Address 908 Palace Bldg., Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed April 13 1955

Application for plugging filed April 13, 1955

Application for plugging approved April 13, 1955

Plugging commenced April 13, 1955

Plugging completed April 13, 1955

Reason for abandonment of well or producing formation
commercial quantity of oil not found

If a producing well is abandoned, date of last production X 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	217'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud from 3690 to 210'. Set wooden plug with 15 sacks cement. Second plug at 40' and capped with 10 sacks cement.

RECEIVED
4/20/55

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor K & E Drilling, Inc.
Address 1006 Central Bldg. Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Dale Silcott

(employee or owner or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale Silcott

1006 Central Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of April, 1955

My commission expires June 25, 1956

Frances Mader
Notary Public.

PLUGGING
FILE SEC 26 T 9 R 19W
BOOK PAGE 112 LINE 8

15-163-00883-00-00

HERMAN GEORGE KAISER
Thomas #1

Ne NW SE Sec. 26-98-19W
Rocks County, Kansas


Comm: 4-4-55
Comp: 4-13-55
Total Depth: 3690'

Casing Cement
8 5/8" Set @ 217' 140 sacks

<u>FORMATION</u>	<u>DEPTH</u>
Sand	0 - 65
Shale & sand	65 - 180
Shale	180 - 217
Shale & shells	217 - 1012
Sand	1012 - 1263
Red bed	1263 - 1535
Anhydrite	1535 - 1560
Shale & shells	1560 - 2020
Shale & lime	2020 - 2330
Lime & shale	2330 - 2435
Shale - lime	2435 - 2740
Lime	2740 - 2935
Shale - lime	2935 - 3245
Lime	3245 - 3297
Lime & shale	3297 - 3390
Lime	3390 - 3565
Lime & shale	3565 - 3600
Lime	3600 - 3603
Conglomerate	3603 - 3670
Lime	3670 - 3690

STATE OF KANSAS)
) SS
SEDGWICK COUNTY)

I hereby certify that the above information is true and correct to the best of my knowledge.



Subscribed and sworn to before me this 18th day of April, 1955.


Notary Public

My commission expires: June 25, 1956

RECEIVED
STATE OF KANSAS

APR 20 1955

Notary Public

PLUGGING
FILE 26 9 19W
DATE 112 LINE 8

STATE OF KANSAS

INVOICE

April 18, 1955 _____ 19 _____

To: Herman Geo. Kaiser
908 Blace Bldg.
Tulsa, Oklahoma

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

For: PLUGGING _____ ASSESSMENT AS FOLLOWS:

Thomas #1
NE NW SE 26-9-19W
Rooks County
File No. 112-8 \$25.00

NOTE: WE ALSO NEED A WELL PLUGGING APPLICATION, WELL LOG, & WELL PLUGGING RECORD ON THIS WELL TO COMPLETE OUR FILE.

pd
Ch # 9096
4-25-55
JH
e-15

TO INSURE CORRECT APPLICATION KINDLY
RETURN PINK COPY WITH REMITTANCE

IN PAYMENT OF:

DETACH BEFORE DEPOSITING

Thomas #1 (Dry)
Plugging Assessment

\$25.00 ✓

P-160

HERMAN GEO. KAISER, OIL PRODUCER

CHECK N^o 9096