


15-163-02791-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD



Rooks County, Sec. 26 Twp. 9 Rge. 19 (E) (W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines NE SE NW
Lease Owner Petroleum, Inc.
Lease Name Jelinek Well No. 2
Office Address 100 Derby Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 9, 19 51
Application for plugging filed January 9, 19 51
Application for plugging approved January 9, 19 51
Plugging commenced January 9, 19 51
Plugging completed January 9, 19 51
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3608 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	190'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Wooden plug set at 190'. Placed one sack hulls on top of plug. Cemented and displaced through drill pipe 15 sax. Filled hole with heavy mud to 40' and 1/2 sack hulls on top of plug. Filled hole to surface with cement.

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Petroleum, Inc.
Address 100 Derby Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Eric H. Jager (employee of owner) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Eric H. Jager
100 Derby Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 16th day of January, 19 51

My commission expires October 13, 1954

Charlotte Heidman Notary Public.

PLUGGING
FILE SEC 26 T 9 R 19 W
BOOK PAGE 55 LINE 15

STATE CORPORATION COMMISSION
JAN 18 1951
WICHITA, KANSAS

DRILLER'S LOG
 PETROLEUM, INC. - - -
 #2 Jelinek
 NE SE NW - Section 26-9S-19W
 Rooks County, Kansas

0	150	Surface sand & shale
150	200	Shale & shells
200	400	Shale & shells
400	1000	Shale, Sand & shells
1000	1245	Sand
1245	1275	Shale & shells
1275	1390	Shale & shells
1390	1515	Red Bed
1515	1555	Anhydrite
1555	1595	Shale & shells
1595	1845	Shale & shells
1845	1980	Shale & shells
1980	2075	Lime & shale
2075	2240	Lime & shale
2240	2380	Lime & shale
2380	2495	Lime & shale
2495	2635	Lime & shale
2635	2730	Lime & shale
2730	2830	Shale & shells
2830	2955	Shale & shells
2955	3045	Shale & shells
3045	3135	Shale & shells
3135	3165	Lime & shale
3165	3227	Lime
3227	3275	Lime & shale
3275	3317	Lime & shale
3317	3356	Lime & shale
3356	3396	Lime & shale
3396	3426	Lime & shale
3426	3490	Lime
3490	3535	Lime & shale
3535	3580	Lime & shale
3580	3593	Lime & shale
3593	3596	Lime
3596	3608	Lime
3608		ROTARY TOTAL DEPTH

COMMENCED: 12/28/50
 COMPLETED: 1/10/51

TOPS:
 Heeb. 3304
 Tor. 3324
 K. C. 3343
 Cong. 3581
 Arb. 3589 (-1428)
 RTD 3608

CASING RECORD:
 Set 8-5/8" surface casing
 @ 1951 with 100 sacks cement
 and 1 CC.
 D & A

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the #2 Jelinek, located in the NE SE NW of Section 26-9S-19W, Rooks County, Kansas.

ANSCHUTZ DRILLING COMPANY, INC.
 BY: *M. W. Smith*
 M. W. Smith

Subscribed and sworn to before me this 12th day of January, 1951.

Patricia Stecker
 Notary Public

My commission expires January 21, 1954.

RECEIVED
 STATE CORPORATION DIVISION
 1/18/51
 JAN 18 1951
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 26 T 9 R 19W
 #30K FILE 55 INT 15