


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County, Sec. 26 Twp. 9 Rge. (E) 19 (W)

Location as "NE/CNW&SW" or footage from lines SW NE SW
Lease Owner Chief Drilling Company
Lease Name Snee Well No. 1
Office Address P.O. Box 787, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 19
Application for plugging filed April 17 19 64
Application for plugging approved 19
Plugging commenced April 19 19 64
Plugging completed April 23 19 64
Reason for abandonment of well or producing formation depleted

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3635 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	204	8 5/8"	204	none
		0	3634	4 1/2	3634	3120.67

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Push plug to 3340', set 10' rock bridge and dump 4 sacks of cement.

Mix 25 sacks of mud at 640'. Lay down 2 joints of pipe. Mix 20 sacks of cement at 580'. Pull 11 joints of pipe. Mix 20 sacks of cement at 200'. Pull 7 joints of pipe. Cap hole with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
5/11/64
MAY 11 1964

Name of Plugging Contractor Pipe Pullers, Inc. (If additional description is necessary, use BACK of this sheet)
Address Box 486, Ellinwood, Kansas
CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Dean Wells (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Wells
Ellinwood, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 28 day of April, 19 64

My commission expires July 7, 1964 Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
APR 30 1964

15-163-02853-00-00

WELL LOG

CONSERVATION DIVISION
Wichita, Kansas

Chief Drilling Co., Inc.
Box 797
Great Bend, Kansas

SMEE #1
SW NE SW Sec. 26-9S-19W
Rooks County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 12/12/63
Completed: 12/21/63

Casing Record: 8-5/8" @ 204 w/175 sacks Sunset Cement.
4-1/2" @ 3633 w/135 sacks Common Salt Saturated Cement.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Surface Sand & Shale	0	204	2159 Gr.
Shale & Shells	204	1005	2161 D.F.
Sand	1005	1190	2164 K.B.
Shale & Shells	1190	1518	
Anhydrite	1518	1560	
Shale & Shells	1560	2290	
Shale & Lime Streaks	2290	2305	
Lime & Shale	2305	2500	
Shale & Lime Streaks	2500	2600	
Lime & Shale	2600	2750	
Lime	2750	2805	
Shale & Lime Streaks	2805	3101	
Lime	3101	3308	
Shale & Lime	3308	3349	
Lime	3349	3566	
Lime & Shale	3566	3588	
Cherty Conglomerate	3588	3613	
Dolomite	3613	3635	
Total Depth	3635		

<u>FORMATION TOPS</u>	
Anhydrite	1518 + 646
Topeka	3101 - 937
Heebner	3308 - 1144
Toronto	3330 - 1166
Lansing	3349 - 1185
Base Kansas City	3566 - 1402
Conglomerate	3588 - 1424
Arbuckle	3613 - 1449
Total Depth	3635 - 1471

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the SW NE SW Sec. 26-9S-19W, Rooks County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

V. Richard Hoover
V. Richard Hoover, President

Subscribed and sworn to before me this 24th day of December, 1963.

Carmen R. Cook
Carmen R. Cook, Notary Public

My commission expires: Jan. 26, 1967.

FROM **DARBY PETROLEUM CORPORATION**

STATEMENT OF ACCOUNT COVERED
BY THIS VOUCHER

			ACCOUNTS PAYABLE RECORD	D 132 44
DATE	INVOICE NUMBER	ORDER		

5-4	FILE 115-3	PLUGGING ASSESSMENT: SMEE # 1 - ROOKS COUNTY	\$ 25.00
-----	------------	---	----------

IF INCORRECT, PLEASE RETURN AT ONCE. IF CORRECT, DETACH STATEMENT BEFORE PRESENTING CHECK. NO RECEIPT IS NECESSARY