

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County. Sec. 26 Twp. 9S Rge. (E) 19 (W)

Location as "NE/CNW&SW" or footage from lines. NE NE SW
Lease Owner Kathol Petroleum, Inc.
Lease Name PYWELL Well No. 1
Office Address 900 Sutton Place - Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1/3 1969
Application for plugging filed 1/3 1969
Application for plugging approved 1/3 1969
Plugging commenced 1/3 1969
Plugging completed 1/3 1969
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey - Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3658 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	208'	8-5/8"	208'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Wooden plug set @ 720'
Mixed 70 sacks cement through drill pipe
Wooden plug set @ 180'
Mixed 20 sacks cement through drill pipe
Wooden plug set @ 40'
Mixed 10 sacks cement through drill pipe

RECEIVED
STATE CORPORATION COMMISSION
FEB 11 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.
Address Box 797 - Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Jim Robinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson
Box 797 - Great Bend, Kansas 67530 (Address)

SUBSCRIBED AND SWORN to before me this 3rd day of January, 1969

Carmen R. Cook Notary Public.

Dec. 12, 1970



15-163-20166-20-00

KATHOL PETROLEUM, INC.

DRILLERS LOG

No. 1 PYWELL

NE NE SW Section 26-9S-19W

Rooks County, Kansas

Commenced: 12/21/68
Completed: 1/3/69
Elevation: 2165' KB

<u>FROM</u>	<u>TO</u>	<u>FORMATION</u>	<u>REMARKS:</u>
0	209	Shale & sand streaks	Set 8-5/8" surface casing at 208' w/159 sx quik set cement.
209	520	Shale	
520	1025	Shale & sand	<u>SAMPLE TOPS:</u> Anhydrite 1225' Topeka 3099' (- 934) Heebner 3307' (-1142) Toronto 3328' (-1163) Lansing 3349' (-1184) Base/K.C. 3552' (-1387) Cong. 3586' (-1421) Arbuckle 3626' (-1461) TD 3658' (-1493)
1025	1240	Sand	
1240	1516	Red Bed & Shale	
1516	1559	Anhydrite	
1559	2230	Shale & shells	
2230	3370	Shale & lime	
3370	3475	Lime	
3475	3520	Lime & Chert	
3520	3592	Lime	
3592	3626	Conglomerate	
3626	3658	Arbuckle	
3658		R.T.D.	

RECEIVED
STATE CORPORATION COMMISSION
FEB 11 1969
CONSERVATION DIVISION
Wichita, Kansas


I certify to the best of my knowledge and belief, the above represents a true and accurate driller's log record of the captioned well.

Don Shawver
Don Shawver

STATE OF KANSAS) SS
COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 10th day of February, 1969.

Dixie Lee Brown
Dixie Lee Brown, Notary Public



My Commission Expires: June 17, 1972.