


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks County, Sec. 26 Twp. 9S Rge. 19W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SE SW

Lease Owner Black Petroleum, Inc.

Lease Name Pywell Well No. 1

Office Address Suite 450, 200 West Douglas, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed February 17 19 70

Application for plugging filed February 17 19 70

Application for plugging approved February 17 19 70

Plugging commenced February 17 19 70

Plugging completed February 17 19 70

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3437 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	215	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug at 685', 70 sacks cement
plug at 210', 20 sacks cement
plug at 40', 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
FEB 25 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____

Address _____

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Don Gardner

(employee of owner) or (~~owner~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

Suite 250, 200 West Douglas, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 18th day of February, 19 70

My commission expires December 14, 1973

[Signature] Notary Public.

15-163-20295-00-00

DRILLERS LOG

#1 PYWELL
SE SE SW Section 26-9S-19W
Rooks County, Kansas

OPERATOR: Black Petroleum, Inc.
Suite 450, 200 West Douglas
Wichita, Kansas

CONTRACTOR: Dunne-Gardner Petroleum, Inc.
Suite 250, 200 West Douglas
Wichita, Kansas

COMMENCED: February 13, 1970

COMPLETED: February 17, 1970


CASING RECORD: 8-5/8" @ 215' w/175 sacks

<u>FROM</u>	<u>TO</u>	<u>DESCRIPTION</u>
0	145	Sand and clay
145	215	Shale and shells
215	830	Clay and shale
830	1035	Shale and shells
1035	1255	Sand
1255	1552	Red bed and shale
1552	1587	Anhydrite
1587	2165	Shale and shells
2165	2400	Shale and lime
2400	2765	Lime and shale
2765	3433	Lime and shale
3433	3437	Lime
		Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION
FEB 25 1970
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct log to the best of my knowledge and belief.

DUNNE-GARDNER PETROLEUM, INC.

Don Gardner

Subscribed and sworn to before me this 18th day of February, 1970

My commission expires:
December 14, 1973


Notary Public