

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-20533-00-00

API NUMBER 15-163-20,553

LEASE NAME Benoit

WELL NUMBER #1

SPOT LOCATION S/2-NE-NE

SEC 26 TWP. 9 RGE. 19 (E) or (W)

COUNTY Rooks

Date Well Completed _____

Plugging Commenced 4-24-86

Plugging Completed 4-30-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR John O. Farmer, Inc.

ADDRESS Box 352, Russell, Ks. 67665

PHONE # (913-483-5243) OPERATORS LICENSE NO. 5135

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Six (6)

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing formation _____ Depth to top _____ bottom _____ T.D. 3574'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	276'	None
				5-1/2"	3572'	992.17'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Dumped sand to 3250' and 5 sacks cement. Shot casing at 1500' and 1000'. Pulled 32 joints of 5-1/2" casing. Halliburton swueezed well with 4 sacks hulls, 35 sacks gel, 100 sacks cement blended with 1 sack hulls, 5 sacks gel and 80 sacks 60/40 posmix cement with 6% added gel and 3% calcium chloride. Maximum pressure 700 psi. and shutin 150 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Ct. Bend, Ks. 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

STATE CORPORATION COMMISSION
5/09/86
MAY 09 1986

(Signature) James W. Rockhold
(Address) James W. Rockhold
Box 698, Ct. Bend, Ks. 67530

CONSERVATION DIVISION
Wichita, Kansas
SUBSCRIBED AND SWORN TO before me this 6th day of May, 1986

STATE NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-87

My Commission expires:

Iona M. Leatherman
Notary Public

15-163-20553-00-00

DRILLERS LOG

BENOIT "B" #1

CASING RECORD:	OPERATOR:	John O. Farmer, Inc.	DESCRIPTION:
206' w/ 8-5/8"	CONTRACTOR:	John O. Farmer, Inc.	C S/2 NE NE
Cemented w/ 150 sx.	COMMENCED:	December 30, 1974	Sec. 26-9S-19W
3572' w/ 5 1/2"	COMPLETED:	January 7, 1975	Rooks County, Ks.
Cemented w/ 100 sx.			
TOTAL DEPTH:			
3574'			

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale	312	680	
Shale & Sand	680	1000	
Sand	1000	1235	
Shells & Red Bed	1235	1290	
Red Bed	1290	1509	
Anhydrite	1509	1546	
Shale & Shells	1546	2290	
Shale & Lime	2290	2995	
Lime & Shale	2995	3370	
Lime	3370	3510	
Lime & Shale	3510	3564	
Lime	3564	3574	
Total Depth	3574		


I certify that this is a true and correct copy of the above log to the best of my knowledge.

JOHN O. FARMER, INC.

By John O. Farmer
 John O. Farmer
 President

Subscribed and sworn to before me this 9th day of January, 1975.

My Commission Expires:
 February 15, 1975



Helen Carlson
 HELEN CARLSON - NOTARY PUBLIC