

STATE OF KANSAS  
 STATE CORPORATION  
 COMMISSION  
 130 S. Market, Room 2078  
 Wichita, KS 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-163-01697-00-00

LEASE NAME Bullock \* KCC CAP

WELL NUMBER #1

2310' Ft. from S Section Line

2970' Ft. from E Section Line

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to  
 Cons. Div. Office within  
 30 days

LEASE OPERATOR OXY USA Inc.

SEC 27 TWP 9 RGE 19W E or W

ADDRESS 110 S. Main # 800

COUNTY Rooks

PHONE# (316 265-5624 Operators License 5447

Date Well Completed 04/17/48

Character of Well oil

Plugging Commenced 04/04/96

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 04/04/96

The plugging proposal was approved on 04/04/96 (Date)

by Dennis Hamel (KCC District Agent's name).

Is ACO-1 filed? no If not, is well log attached? no

Producing Formation Oread Depth to Top 3296' Bottom 3320 T.D. 3661'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Oread		3296'	3320'	8 5/8"	315'	
				5 1/2"	3661'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from      Feet to      Feet each set.

See back for details.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No.     

Address 332 W Wichita, Russell, Kansas 67665-0031

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc  
 STATE OF Kansas COUNTY OF Sedgwick, ss.

Timothy J. Voss (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Timothy J. Voss

(Address) 110 S. Main Wichita Kansas 67202

SUBSCRIBED AND SWORN TO before me this 2nd day of July, 19 96

Stephen E. Darwin  
 Notary Public

STEPHEN E. DARWIN  
 NOTARY PUBLIC  
 STATE OF KANSAS  
 My Appt. Exp. 3-9-99

My commission Expires: Stephen E. Darwin 3-9-99

04/23/96 JOB: Plug and Abandon; CMIC: JD Hininger  
P&A - Perf. 5 1/2" @ 2200' - 1565' - 300' w/2 holes at each ent. -  
cemented down 8 5/8" w/50 sks 60/40 pozmix containing 10% gel. (Allied)  
plus 200# hulls - max psi. 300 - shut in 200 psi. - pumped down 5 1/2"  
w/325 sks. plus 300# hulls - max psi. 500 - shut in 300 psi. - Plugged  
@ 11:00 AM 4/4/96 - State Wittness - Dennis Hamel  
L/E \$ 3488; MAT \$ 1254; CUM: L/E \$ 3488, MAT \$ 1254, TOT \$ 4742;