

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 1 1964
9-1-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name D & D Drg Co & Lee Phillips

Complete Address: 307 Schweiter Bldg Wichita, Kansas

Lease Name Mc Clellan Well No. 1

Location NW NE NW Sec. 9 Twp. 9 Rge. (E) (W) 19

County Rooks Total Depth 3510

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: D & D Drg Co & Globe Cementing Co

Address: same License No.

Operation Completed: Hour 2PM Day 25 Month 8 Year 64

The Above well was plugged as follows:

8 5/8" 217' circulated with cement.

Circulated hole with heavy mud, set plug at 540' and displaced 20 sax cement through drill pipe, heavy mud to 180', set plug and displaced 20 sax cement through drill pipe, heavy mud to 35', set plug, hulls and filled to bottom cellar with cement.

Cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

DATE 9/1/64
INV. NO. 9445-W

Signed: Edwin Kelly
Well Plugging Supervisor