

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JAN 4 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Continental Oil Company
Complete Address 3535 NW 58th ST. Oklahoma City, Oklahoma 73112
Lease Name Barry L-KC Unit Well No. 638
Location SW NW SW Sec. 2 Twp. 9 Rge. (E) (W) 19
County Rooks Total Depth 3517'
Abandoned Oil Well KCCOB Gas Well Input Well SWD Well D & A
Other well as hereafter indicated _____
Plugging Contractor Pipe Pullers Inc.
Address Box 486 Ellinwood, Kansas License No. 462
Operation Completed: Hour 5 P Day 30 Month 12 Year 1971

The above well was plugged as follows:

Total Depth 3517' 10 3/4 csg set at 200' cwc 200 sk.
6" csg set at 3504' cw 300 sk cmt.
6" csg PBTB 3442' and perf. (3231)
Filled 6" csg W/sd (3200-3442) Dumped 6 sk cmt W/dump bailer. (3165-3200)
Squeezed 6" csg at 895' with 15 sk gel W/5 sk hulls and 100 sk common cmt. 600 PSI
Circulated 10 3/4 csg from 207' to surface with 125 sk cmt W/6% added gel.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Mansur
Well Plugging Supervisor

DATE 1-9-72
INV. NO. 4848-W