

15-163-02294-00-00-*R*

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 15 1976
1-15-76
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Continental Oil Company

Complete Address 3535 NW 58th St., Oklahoma City, Oklahoma 73112

Lease Name Berry Lansing KC Unit Well No. 121

Location C NE NE NE Sec. 11 Twp. 9 Rge. 10 (E) 19 (W) 19 *KCC AB.*

County Rooks Total Depth 3484'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pipe Pullers, Inc.

Address Box 486, Ellinwood, Kansas 67526 License No. 462

Operation Completed: Hour 10 A Day 13 Month 1 Year 1976

The above well was plugged as follows:

Total Depth 3484' 10 3/4 csg set 240' cwc 240 sk.

6" csg set 3484' cw 200 sk cem.

6" csg PBD 3444' & PFS (3426'-3220')

Filled 6" csg W/sd (3444'-3200') dumped 5 sk cem. W/dump bailer. (3200'-3165')

Cutoff & recovered 618' of 6" csg.

Mixed & pumped down 10 3/4 csg with 25 sk gel & water -300 lbs hulls -120 sk

50-50 poz cem W/6% total gel. PP 400 lbs. SIP 100 lbs. By Sun Cem. Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Leo Wanner*
Well Plugging Supervisor

DATE 1-15-76

INV. NO. 25-73-W