

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION SW NW NE

SEC. 12 TWP. 9 RGE. 19

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Jelinek

Operator W. J. Wickizer Address Wakeeney, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3484 Feet.

Plugging Contractor Arnett Casing Pulling

Plugging Contractor's License No. 265

Address \_\_\_\_\_

(Describe briefly the manner in which the well was plugged)

8 5/8" at 274' circulated with cement - 4 1/8" at 3479'

with 100 sax cement behind - perforated at 3209' - perforations  
squeezed off with cement .

Filled with sand and set plug at 3190' - set 4 sax cement with

dump bailer - pulled 550' 4 1/8" - filled hole with mud to

275', set rock and 15 sax cement - mud to 35', set rock and

10 sax cement to bottom cellar.

District Conservation Agent

Date \_\_\_\_\_

2-14-55

2/18/55

**PLUGGING**  
FILE SEC 12 T 9 R 19W  
BOOK PAGE 91 LINE 35