



Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
10/15/74  
OCT 15 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Barnett Oil, Inc.  
Complete Address 411 First Nat'l Bk. Bldg., Wichita, Kansas 67202  
Lease Name Jelinek Well No. 1  
Location NW SW NW Sec. 12 Twp. 9 Rge. (E) (W) 19  
County Rooks Total Depth 3465'  
Abandoned Oil Well XX Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_  
Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor Pipe Pullers, Inc.  
Address Box 486, Ellinwood, Kansas 67526 License No. 462  
Operation Completed: Hour 5 P Day 11 Month 10 Year 1974

The above well was plugged as follows:

Total Depth 3465' 8 5/8 csg set at 160' cwc 125 sk.  
5 1/2 csg set at 3461' cw 100 sk cem.  
Filled 5 1/2 csg with sand (3465-3420') dumped 4 sk cmt W/dump bailer. (3390-3420)  
5 1/2 csg squeezed thru "Dak. Sec." & circ. to surface. No pipe recovered.  
Filled 5 1/2 csg with mud to 625' -set rock & sand bridge (625-600)  
Filled with readymix cem. from 600' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/16/74

INV. NO. 101-W

Signed: Leo J. Massey  
Well Plugging Supervisor