

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE NE SW

SEC. 12 TWP. 9 RGE. 19

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Hilgers 'C'

Operator Trans Era Pet Inc Address Russell, Kans

Field _____ County Rooks

Total Depth 3528 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 217' circulated with cement - 5 1/2" at 3481'

with 100 sax cement behind.

Mud and rock to 3425 set Lane Wells plug - Perforations

3305' - mud and rock to 3290' set 5 sax cement with dump

bailer, pulled 2700' 5 1/2", filled with mud to 217', set rock

and 15 sax cement, mud to 35', set rock and 10 sax cement

to bottom cellar,

PLUGGING
FILE SEC 12 T 9 R 19
BOOK PAGE 11 LINE 40

STATE CORPORATION COMMISSION
NOV 25 1952
CONSERVATION DIVISION
Wichita, Kansas

[Signature]
District Conservation Agent
Date 11-22-52