

10
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

4/27/64
APR 27 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Chief Drg Co

Complete Address: Box 787 Great Bend, Kansas

Lease Name Smee Well No. 1

Location SW NE SW Sec. 26 Twp. 9 Rge. (E) (W) 19

County Rooks Total Depth 3635

Abandoned Oil Well Gas Well Input Well SWD Well D & A x

Other well as hereafter indicated:

Plugging Contractor: Pipe Pullers Inc

Address: Ellinwood, Kansas License No. 462

Operation Completed: Hour 4PM Day 23 Month 4 Year 64

The Above well, was plugged as follows:

8 5/8" 204' circulated with cement - 4 1/2" 3634' with 135 sax cement - Perf 3352'.

Filled with sand to 3340', set 4 sax cement with dump bailer - pulled

3104' 4 1/2" to 640', circulated hole with heavy mud through 4 1/2" at 640' (25 sax Gel), displaced 20 sax cement through 4 1/2" at 580', heavy mud to 200', displaced 20 sax cement through 4 1/2" at 200', heavy mud to 35', set bridge and 10 sax cement to bottem cellar.

Mudding and cementing by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edon Terry*
Well Plugging Supervisor

DATE 4/28/64
INV. NO. 9036-u