

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NW NW NE

SEC. 26 TWP. 9 RGE. 19

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Jelinek

Operator Petroleum Inc Address Wichita, Kans

Field _____ County Rooks

Total Depth 3558 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 181' circulated with cement - 5 1/2" at 3555' with
100 sax cement behind.

Filledw with chat to 3540', set 4 sax cement with dump bailer,
pulled 2900' 5 1/2", filled hole with mud to 180', set rock and 10 sax
cement, filled with mud to 55', set rock and 10 sax cement
to bottom cellar.

District Conservation Agent

Date 10-15-51

PLUGGING
FILE SEC 26 T 9 R 19 OCT 22 1951
BOOK PAGE 117 CONSERVATION DIVISION
Wichita, Kansas