

LEASE NAME Cooley A

WELL NUMBER 7

 Ft. from S Section Line

SW SE SW Ft. from E Section Line

SEC. 17 TWP. 9 RGE. 21 (E) or (W)

COUNTY Graham County

Date Well Completed 5-23-50

Plugging Commenced 10-14-94

Plugging Completed 10-14-94

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Berexco, Inc.

ADDRESS Box 723

PHONE# (913) 628 6101 OPERATORS LICENSE NO. 5363

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-14-94 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3817

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	17 1/2	8 5/8		
	Casing	0	3810	5 1/2		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Rig up Mercury perf. 2 shots at 1800', 1050' and 200'. Run 110 jt. tubing openended tag at 3447.0
Pull 1 jt. 3407.63. Spot 75 sk. 60/40 pos 10% gel with 300# hulls. Pull 32 its. 2404.68'.
Spot 75 sk. 60/40 10% gel with 100# hulls. Pull 32 its. 1401.29'. Circulate to surface with
90 sk. 60/40 pos 10% gel with 100# hulls. Pull tubing. Hook to 5 1/2 circulate to surface on 8 5/8
with 60 sk. 60/40 10% gel. Shut in 8 5/8 and 5 1/2 no pressure.

Name of Plugging Contractor Berexco, Inc. License No. 5363

Address Box 723 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well as filed with the same are true and correct, so help me God.

(Signature) Ted Crawford

(Address) Box 723 Hays, KS 67601

SWORN TO before me this 17 day of October, 19 94

Rosemary Smith
 Notary Public

NOTARY PUBLIC - State of Kansas
 ROSEMARY SMITH
 My Appointment Expires 5-1-1995

USE ONLY ONE SIDE OF EACH FORM

5-1-1995