

LEASE NAME Cooley A

WELL NUMBER 6

         Ft. from S Section Line

         NE NW SW Ft. from E Section Line

SEC. 17 TWP. 9 RGE. 21 (E) or (W)

COUNTY Graham

Date Well Completed 4-13-50

Plugging Commenced 6-23-95

Plugging Completed 6-23-95

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Berexco, Inc.

ADDRESS Box 723 Hays, Kansas 67601

PHONE# (913) 628 6101 OPERATORS LICENSE NO. 5363

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-23-95 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 3844

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0	180	8 5/8		
	Casing	0	3824	5 1/2		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from          feet to          feet each s  
 Run tbg. to 3786'. Mix 75 sk. 60/40 pos. Pull 33 jts. Mix 75 sk. 60/40 pos. Pull 33 jts.  
 Mix 110 sk. 60/40 pos. Circulate cement. Pull          rest of tubing. Hook to surface. Mix 50  
 sks. 60/40 pos. Hook to casing. Mix 40 sk. 60/40. Shut in both sides at 200#.

Name of Plugging Contractor Berexco, Inc. License No. 5363

Address Box 723 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Ellis


Mr. Ted Crawford (Employee of Operator) or (Operator)  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the fac  
 statements, and matters herein contained and the log of the above-described well as filed t  
 the same are true and correct, so help me God.

(Signature) Ted Crawford

(Address) Box 723 Hays, Ks 67601

29 day of June, 19 95

Rosemary Smith  
 Notary Public



My Commission Expires: 5-1-1999

USE ONLY ONE SIDE OF EACH FORM