

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Graham SEC. 23 TWP. 9S RGE. 21 E/W
Location as in quarters or footage from lines:
C S/2 NW SW

Locate Well
correctly on above
Section Platt.

Lease Owner Jolly 'J', Inc.
Lease Name Lewis Family Farms Well No. 1
Office Address 7th & Main, Russell, Kansas 67665
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed 11-19-82
Application for plugging filed 11-19-82
Plugging commenced 11-19-82
Plugging completed 11-20-82
Reason for abandonment of well or producing formation Dry Hole

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ bottom _____ T.D. 3859'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	250'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Mud laden fluid @ 3859' - 3750'
20 sks cement @ 3750'
20 sks cement @ 1770'
100 sks cement @ 1110'
40 sks cement @ 270'
10 sks cement @ 40'
10 sks cement in rathole.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Emphasis Oil Operations

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Joe K. Branum (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Joe K. Branum
P. O. Box 506, Russell, KS 67665-0506
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of November, 19 82



Glenda R. Tiffin
Glenda R. Tiffin, Notary Public.

My Commission expires: February 6, 1984.

RECEIVED
STATE CORPORATION COMMISSION

NOV 29 1982
11-29-82
CONSERVATION DIVISION
Wichita, Kansas

EMPHASIS OIL OPERATIONS
P. O. Box 506
Russell, Kansas 67665-0506

DRILLERS LOG

OPERATOR: Jolly 'J', Inc.
7th & Main
Russell, Kansas 67665

CONTRACTOR: Emphasis Oil Operations
P. O. Box 506
Russell, Kansas 67665-0506

LEASE: Lewis Family Farms WELL: #1

LOCATION: C S/2 NW SW
Section 23-9S-21W
Graham County, Kansas

Total Depth: 3859'

Elevation: 2316' K.B.

Commenced: 11-11-82

Completed: 11-20-82

Casing: 8-5/8" @ 250' with 150 sks cement

Status: Dry Hole

DEPTHS & FORMATIONS


(All measurements from K.B.)

Topsoil & Sand	40'	Shale & Lime	2872'
Sand & Shale	399'	Lime	2972'
Shale	1414'	Shale & Lime	3517'
Shale & Sand	1753'	Lime	3585'
Shale & Lime	1762'	Lime & Shale (R.T.D.)	3859'
Anhydrite	1809'		

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)


RECEIVED
STATE CORPORATION COMMISSION
NOV 29 1982
CONSERVATION DIVISION
Wichita, Kansas

Joe K. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.


Joe K. Branum

Subscribed and sworn to before me this 24th day of November, 1982.

My Commission Expires: February 6, 1984.




Notary Public