

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-103-01753-00-00  
API NUMBER 2-15-48

LEASE NAME Rathbun

WELL NUMBER 15 | KCC ZAP

2970 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 27 TWP. 9S RGE. 20 ~~KC~~ or (W)

COUNTY Rooks

Date Well Completed 2-15-48

Plugging Commenced 7-30-92

Plugging Completed 7-30-92

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR AFG Energy, Inc.

ADDRESS P.O. Box 605, Russell, KS 67665

PHONE# (313) 625-6374 OPERATORS LICENSE NO. 3456

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-30-92 (date)

by Dennis Hamel (KCC District Agent's Name).

is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Arbuckle-LKC Depth to Top 3601' Bottom 3852' T.D. 3852'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	oil & water	3804	3852	8 5/8"	131	None
L-KC	oil & water	3601	3686	5 1/2"	3804	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set  
Perforated 3 holes - 1770'. Ran tubing to 3690' - spotted 100 sx. 60/40 Poz, 10% gel, 1/4# flow seal and 1 sx. hulls. Pulled tubing to 1500' and circulated hole full - took 50 sxs. of same. Pulled tubing and hooked to 5 1/2" casing. Pumped 100 sx. same at Max. pressure - 1000# SIP-800#. 8 5/8" was full of cement.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. \_\_\_\_\_

Address Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: AFG Energy, Inc.


STATE OF Kansas COUNTY OF Russell, ss.

Terry W. Piesker (Employee of Operator) or \_\_\_\_\_  
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well as the same are true and correct, so help me God.

(Signature) Terry W. Piesker

(Address) P.O. Box 605, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 10th day of August, 1992



Pamela K. Steckel  
Notary Public

My Commission Expires: 11-19-92