


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec. 8 Twp. 9S Rge. (E)19 (W)
Location as "NE/CNW/SW" or footage from lines. NW NW SW
Lease Owner Rains & Williamson Oil Co.
Lease Name Stull Well No. 1
Office Address 1425 Wichita Plaza Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-26 19 66
Application for plugging filed 11-26 19 66
Application for plugging approved 11-26 19 66
Plugging commenced 11-26 19 66
Plugging completed 11-26 19 66
Reason for abandonment of well or producing formation no oil or gas found
in commercial quantities
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3565 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	228.95	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pushed plug to 540'. Cemented through drill pipe with 25 sacks. Mud back to 220'. Pushed plug and cemented thru drill pipe with 20 sax. Mud back to 40'. Set solid bridge and capped with 8 sax. 2 sax. in rat hole. Plugging completed at 5:00 P.M.

DEC 2 1966
12-2-66
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co.
Address 1425 Wichita Plaza Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Wilson Rains (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
1425 Wichita Plaza Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 30 day of November, 19 66

My commission expires 3-3-70

Mary J. Brown
Mary J. Brown
Notary Public.

ROTARY DRILLING LOG

Operator: Rains & Williamson Oil Co. Contractor: Rains & Williamson Oil Co.
 #1 Stull Commenced: 11-19-66
 NW NW SW Sec. 8-9S-19W Completed: 11-26-66
 Rooks County, Kansas Remarks: Set 228.95' of 8-5/8" surface
 pipe with 165 sacks GL-3.

FORMATIONS

Soil & Rock	75°
Shale	945°
D. Sand	1180°
Shale	1464°
Anhydrite	1506°
Red Bed	1860°
Shale	2185°
Lime & Shale	2335°
Lime w/Shale	2480°
Lime & Shale	2860°
Lime W/Shale	3010°
Lime & Shale	3260°
Lime w/Shale	3325°
Lime & Shale	3490°
Lime w/Shale	3525°
Lime	3545°
Arb. Lime	3565°
Rotary Total Depth (D&A)	3565°

RECORDED
 & INDEXED
 DEC 2 1966
 12-2-66
 CONSERVATION DIVISION
 Wichita, Kansas

We certify the above log is true
 and correct to the best of our
 knowledge and belief.

RAINS & WILLIAMSON OIL CO.

Wilson Rains
 Wilson Rains

I, _____, do hereby certify and sworn to before me, a Notary Public in and for the State of
 Kansas, County of Sedgwick, this 30th day of November 1966.

My Commission Expires:

8-1-70

Mary J. Brown
 Mary J. Brown, Notary Public