

**Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas**

NORTH


**Locate well correctly on above  
Section Plat**

15-163-00177-00-00

## Rooks

County. Sec. 8 Twp. 9S Rge. (E) 19 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE NE

Lease Owner PETROLEUM, INC.

Lease Name McClellan

Well No. 1

Office Address 100 Derby Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) ..... Dry Hole

Date well completed.....6/28<sup>19</sup> 49

Application for plugging filed.....6/28/19 49

Application for plugging approved \_\_\_\_\_ 6/28 19 49

Plugging commenced 6/28/1949

Plugging completed. 6/28/49

Reason for abandonment of well or producing formation.

If a producing well is abandoned, date of last production..... 19.....

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well. C. D. Stough, Box 207, Great Bend, Kansas

Producing formation..... Depth to top..... Bottom..... Total Depth of Well 3500 Feet

Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to .....feet for each plug set.

Filled hole with heavy mud to 208'. Placed wooden plug at 208'. Mixed and dumped

15 sacks cement. Filled hole with heavy mud to 30'. Placed wooden plug at 38'.

Filled hole with cement to Bottom Cellar.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to.....PETROLEUM, INC.

Address.....100 Derby Building, Wichita 2, Kansas

STATE OF KANSAS ~~IN THE DISTRICT COURT OF THE~~ COUNTY OF SEDGWICK, ss.  
Eric H. Jager

.....(employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-  
described well as filed and that the same are true and correct. So help me God.

(Signature)

100 Derby Building, Wichita 2, Kansas

(Address)


SUBSCRIBED AND SWORN to before me this 28 day of June 19 49

My commission expires..... June 7, 1952.

-----  
*Notary Public.*

22-5133-s

9-48—10M



WELL LOG McCLELLAN NO. 1

Lease Owners: PETROLEUM, INC.

Sec. 8, Twp. 9S, Range 19W

Contractor: Drillers, Inc.

Location: NE NE NE

Total Depth: 3500'

County: Rocks - Kansas

Commenced: June 10, 1949

Elevation: 2016 D.F.

Completed: June 20, 1949

Production: Dry Hole

Casing: 20 1/2" of 8 5/8"

Figures below indicate bottom of formation:

40	Surface rock	3205	Lime & shale
125	Shale	3500	Lime
505	Shale & shells		
610	Sand	3500	Rotary Total Depth
830	Shale & red bed		
935	Shale & shells		
1180	Sand		
1400	Sand & shale		
1445	Shale		
1485	Anhydrite		
1610	Shale & shells		
1730	Shale		
1785	Lime		
2235	Shale & shells		
2419	Shale & lime		
2435	Lime		
2465	Shale		
2485	Lime		

Tops:

Anhydrite	1485
Topeka	2982
Heebner	3188
Toronto	3212
Lansing	3228
Arbuckle	3473

I hereby certify that this is a true and correct log of the abovementioned well.


PETROLEUM, INC.

Eric H. Jager

STATE OF KANSAS

SS.

SEDGWICK COUNTY



Subscribed and sworn to before me, a Notary Public in said County and State this 20th day of June, 1949.

Notary Public

My Commission expires: June 7, 1952.