

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-163-20,162-00-00
LEASE NAME McClellan (Twin)
WELL NUMBER #1

RECEIVED

DEC 30 2002

12-30-02
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

_____ Ft. from S Section Line
_____ Ft. from E Section Line
SEC. 8 TWP. 9 RGE. 19 (E) or (W)

LEASE OPERATOR Palomino Petroleum, Inc.

COUNTY Rooks

ADDRESS 4924 SE 84th St., Newton, KS 67114-8827

Date Well Completed 02/20/69

PHONE# (316)799-1000 OPERATORS LICENSE NO. 30742

Plugging Commenced 12/23/02

Character of Well Oil

Plugging Completed 12/26/02

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on December 23, 2002 (date)

by Richard Williams (KCC District Agent's Name).

Is ACO-1 filed? Unknown If not, is well log attached? _____

Producing Formation _____ Depth to Top 3513' Bottom 3516' T.D. 3540'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0'	208'	8-5/8"	208'	0'
	Production	0'	3516'	5-1/2"	3516'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Shot tubing off @ 3300' and pull tubing out. Perf. well @ 1925', 1500' & 925'. Run tubing in to 2500', spot 125sx cement w/250# hulls. Pull up to 1500', spot 100sx cement w/250# hulls cement circulated. Pull tubing out. Tied onto 5-1/2", spot 75sx cement w/1000#psi. Shut in @ 500#psi. Tied onto 8-5/8", spot 50sx cement w/200# hulls @ 500#psi. Shut in @ 300#psi. Tore down and moved off.

Name of Plugging Contractor D.S. & W. Well Servicing, Inc. License No. 6901

Address P.O. Box 231, Claflin, KS 67525

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Palomino Petroleum, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Edward S. Nemnich (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

KAREN J. MITCHELL
Notary Public - State of Kansas
My Appt. Expires 4/13/06

(Signature) Edward S. Nemnich
(Address) P.O. Box 231, Claflin, KS 67525

SUBSCRIBED AND SWORN TO before me this 27th day of December, 2002

Karen J. Mitchell
Notary Public

My Commission Expires: April 13, 2006

OR