

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-62-3-117

API NUMBER 15-163-20,180-00-00
 LEASE NAME McClellan

RECEIVED

DEC 30 2002
 12-30-02

KCC WICHITA

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER #2
 _____ Ft. from S Section Line
 _____ Ft. from E Section Line
 SEC. 8 TWP. 9 RGE. 19 (E) or (W)

LEASE OPERATOR Palomino Petroleum, Inc.

COUNTY Rooks

ADDRESS 4924 SE 84th Street, Newton, KS 67114-8827

Date Well Completed 04/24/69

PHONE# (316) 799-1000 OPERATORS LICENSE NO. 30742

Plugging Commenced 12/16/02

Character of Well Oil

Plugging Completed 12/20/02

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on December 17, 2002 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? Yes if not, is well log attached? _____

Producing Formation _____ Depth to Top 3321' Bottom 3408' T.D. 3553'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0'	214'	8-5/8"	214'	0'
	Production	0'	3525'	5-1/2"	3525'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Bottom plug. Sand well back to 3258', spot 5sx cement. Perf. well at 1925', 1500' & 825'. Run tubing in to 2500', spot 100sx cement w/700# hulls. Pull up to 1000', spot 105sx cement w/300# hulls - cement circulated. Pulled tubing out. Lined onto 5-1/2" & pump 55sx cement - had 700#psi. Whit well in @ 400#psi. Lined onto 8-5/8", spot 50sx cement w/200# hulls - had 500#psi on it. Shut in @ 200#psi. Tore down and moved off.

Name of Plugging Contractor D.S. & W. Well Servicing, Inc. License No. 6901

Address P.O. Box 231, Claflin, KS 67525

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Palomino Petroleum, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Edward S. Nemnich (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

KAREN J. MITCHELL
 Notary Public - State of Kansas
 My Appt. Expires 4/13/06

(Signature) Edward S. Nemnich

(Address) P.O. Box 231, Claflin, KS 67525

SUBSCRIBED AND SWORN TO before me this 26th day of December, 2002

Karen J. Mitchell
 Notary Public

My Commission Expires: April 13, 2006

OP